

Model EPD, EPPD




PRO Drainer™
sump & drainage
EBARA International Corporation Standard Pump Division

Features

- High quality stainless steel (Note: Model EPPD has Noryl impeller and diffuser)
- Available in 1/3, 1/2, 3/4, 1 1/2 models
- Single and three phase models available
- Air filled, continuous duty rated, permanent split capacitor motors
- Built-in thermal protection with automatic reset
- Built to operate whether fully or partially submerged
- Oil lubricated double mechanical shaft seal
- Temperature rating to 122°F/50°C; 140°F/60°C intermittent duty
- 20' UL/CSA approved, water resistant #16 AWG cord
- Capacities to 88 GPM, heads to 62 feet

EPD, EPPD Selection Chart



- Empty water storage structures
- Decorative fountains
- Irrigation
- Mound systems, leach fields
- Move water/effluent to sewage systems

